

## GATEWAY WEATHERIZATION INVITATION TO BID

This is an invitation to bid for the following job numbers are listed below in table. Up for bid is Mechanical bid measures for HVAC/Electrical contractors only. All jobs will describe if labor or labor and material will be up for bid per job. Or if material will be provided by Gateway Community Action WX. All bids should be received by 4:30pm on the closed date listed for each job to be eligible. Bids can be emailed to [evan.oneal@gatewaycaa.org](mailto:evan.oneal@gatewaycaa.org) or dropped/mailed to Gateway Community Action located at 151 University Drive, West Liberty, KY 41472.

Email [evan.oneal@gatewaycaa.org](mailto:evan.oneal@gatewaycaa.org) to request a Bid Packet for any of the open jobs or if you have any questions.

Packets that are hand delivered or mailed must be in a sealed envelope with the word BID and the job number on the front. Bid packets will be opened no later than three days after they are due. All bid award notifications will be sent out to all contractors that return a bid for each job and contractors that are listed on Gateway Weatherization's approved contractor list. To apply to be on our approved contractor list for Weatherization jobs please contact Evan O'Neal by phone 1-800-927-1833 or 606-743-3133, also by email at [evan.oneal@gatewaycaa.org](mailto:evan.oneal@gatewaycaa.org) .

### IMPORTANT:

1. You must write your business name on the bid form and it must be signed by someone authorized to do so.
2. All measures must be bid in order for your bid to be eligible.

**WEATHERIZATION CONTRACT JOBS ARE LISTED BELOW**

JOB #	Material up for Bid	Labor up for Bid	Scope of Work	Open Date for Bid	Closing Date for Bid
070122-01	NO	YES	Replace 12kw furnace with 10kw furnace, install new heat pump, install breaker and new drain line to the outside and insulate drain line, and mastic duct plenum. Run flex duct to a room from existing duct run, and mastic a collar and boot before flex duct. Install non fuse disconnect at the water heater, replace old bath fan and install new one with rigid pipe and insulate.	7/13/2022	7/18/2022
072522-05	NO	YES	Install new furnace and duct work , install new breakers in panel to work with correct size for furnace. mastic duct plenum, seal around all new boots into floor registers and insulate duct work. Install bathroom exhaust fan through the roof and install non fuse disconnect at the furnace and hot water heater. Run new drain line to the outside from furnace.	7/29/2022	8/1/2022
072022-03	NO	YES	Replace Thermostat, clean furnace, replace a/coil, check outside unit for freon, and add heat pump risers to unit. Install non fused disconnect at the water heater, install bathroom exhaust fan,	8/4/2022	8/8/2022
081622-09	NO	YES	Replace Heating system, change out of thermostat, install disconnect at hot water heater. Install a bathroom exhaust fan.	08/25/2022	08/29/2022
080922-06	NO	YES	Remove ventless wall heater and replace with direct vented wall heater. install a shut off valve and drip leg at the heater, install a	9/16/2022	09/19/2022

			thermostat in the livingroom and reroute the gas line to heater. Repair baseboard heater thermostat, and install a disconnect at the water heater and correct wiring issues under the house in crawl space.		
092722-13	NO	YES	Replace thermostat, replace existing furnace and old AC unit with a 20k furnace and 3 ton heat pump. Run a new drain line to outside of home and insulate, and replace duct plenum and mastic connection. Run a new line set and recover freon from the old unit. install disconnect on outside unit, new wire will need to be run to outside unit. Install a non fused disconnect at water heater and rix and organize current wires on top of tank. Place a junction box under the crawl space and add a cover lid. Replace existing bathroom fan and run rigid pipe through roof and install a vent cap and seal around lid. add two gain box with blank light switch cover and insert.	9/29/2022	10/3/2022
092122-11	NO	YES	Install new thermostat and replace existing. Replace existing gas furnace with 80k LP furnace 95+ . Cap off return in the furnace closet and install new duct plenum and mastic plenum into duct. Install drip leg and shut off valve, black iron through floor and inside cabinet. install 2 4'' sch 40 pipe through roof and insulate and seal cap. Install new AC unit and line set. Will need to run new 10-2 and install correct breaker to match data plate, install new non fused disconnect within view of outside unit. Install new non fused disconnect at the water heater and add wire connectors where needed. Install new bathroom exhaust no pre existing unit, run 4'' rigid pipe through to roof and	9/29/2022	10/3/2022

			insulate. install roof cap and seal with screws and silicone. Install a 2 gain remodel box and blank insert for fan. Install new kitchen exhaust fan 30" with existing electrical. Add 6" pipe through ceiling and roof and insulate. Place roof cap and seal and insulate pipe.		
072122-04	NO	YES	Replace gas wall heater with new 35kbtu gas direct vent heater. replace ventless wall heater with 15kbtu gas direct vent wall heater. Run a new gas line to the one unit. Add vinyl siding kit for the vent pipe on both heaters. install drip leg and shut off for both heaters. Install bathroom exhaust fan, run new wire to fan, vent through roof with rigid pipe and insulate to r-8	10/20/2022	10/25/2022
091322-10	NO	YES	Replace ventless wall heater with vented gas wall heater, install a bathroom fan. Install new disconnect at hot water heater.	10/20/2022	10/25/2022
101722-14	NO	YES	Install new programmable thermostat. Replace existing furnace with a new heat pump system and run new wiring. Install new disconnect at the hot water heater. Replace existing bath fan.	11/29/2022	12/5/2022
081622-09	NO	YES	Install new programmable thermostat. Replace existing furnace with a new heat pump system and run new wiring. Install new disconnect at the hot water heater. Replace existing bath fan.	11/29/2022	12/5/2022
111622-18	NO	YES	Replace old thermostat with programmable one. Replace furnace with 15k furnace and 2.5 ton heat pump. Run new wire to outside unit and install disconnect. Run new thermostat wire and install correct breaker at box. Replace all floor registers, and install non fused disconnect at hot water heater and change out breaker size. Install new bath fan and run new wire to unit and run	1/11/2023	1/13/2023

			vent to outside with ridgid pipe and insulate to r-8		
111822-19	NO	YES	Replace 12 k furnace, install non fused disconnect by outside unit. run line set and new electrical to heat pump. Replace all floor registers. Install new wire connectors on hot water heater. Run 10-2 wire from the hot water heater to the panel box and install the breaker. Replace broken light switch. Replace existing bath fan with motion sensor fan.	1/20/2023	1/30/2023
111422-15	NO	YES	Install new furnace, run all new eire to unit. Run line set and mastic duct plenum. Install new duct work and thermostat, install non fused disconnect. Fix electrical on porch lights with lids. Replace light fixtures in home, and install new non fused disconnect and add new breaker for correct size. Install new bath fan and insulate.	1/20/2023	1/30/2023
120622-22	NO	YES	Replace thermostat, replace heating system from combo unit to split system and run new wire and install a non fused disconnect and run new drain line and insulate. Install new disconnect on hot water heater. Put main service wire in conduit under floor. Replace old bath fan with new whisper green bath fan.	2/3/2023	2/9/2023