

## GATEWAY WEATHERIZATION INVITATION TO BID

This is an invitation to bid for the following job numbers are listed below in table. Up for bid is Mechanical bid measures for HVAC/Electrical contractors only. All jobs will describe if labor or labor and material will be up for bid per job. Or if material will be provided by Gateway Community Action WX. All bids should be received by the closed date and time listed for each job to be eligible. Bids can be dropped/mailed to Gateway Community Action located at 151 University Drive, West Liberty, KY 41472 ATTN: Evan O'Neal.

Email [evan.oneal@gatewaycaa.org](mailto:evan.oneal@gatewaycaa.org) to request a Bid Packet for any of the open jobs or if you have any questions.

Packets that are hand delivered or mailed must be in a sealed envelope with the word BID and the job number on the front. Bid packets will be opened no later than three days after they are due. All bid award notifications will be sent out to all contractors that return a bid for each job and contractors that are listed on Gateway Weatherization's approved contractor list. To apply to be on our approved contractor list for Weatherization jobs please contact Evan O'Neal by phone 1-800-927-1833 or 606-743-3133, also by email at [evan.oneal@gatewaycaa.org](mailto:evan.oneal@gatewaycaa.org) .

### IMPORTANT:

1. You must write your business name on the bid form and it must be signed by someone authorized to do so.
2. All measures must be bid on in order for your bid to be eligible.

**WEATHERIZATION CONTRACT JOBS ARE LISTED BELOW**

**2024-2025**

JOB #	Material up for Bid	Labor up for Bid	Scope of Work	Open Date for Bid	Closing Date for Bid
020524-14	NO	YES	Replace old thermostat with a T6 programmable thermostat, Replace existing furnace with a new 95 plus sealed combustion high efficiency unit, Use a 2 pipe venting system, Will need to replace pan joisting with return metal duct. Install condensate pump. Furnace will need new wire ran to the breaker box so that it is on a dedicated circuit. Install new drip leg and shut off valve to the furnace. Install central air conditioner. Run new electric service to the breaker box from unit. Install correct sized breakers to match data plate. Install new non fuse disconnect and drain line, drain line will also need to be insulated. Replace water heater single wall venting with B-vent pipe all the way to the outside of roof. Add drip leg and shut off valve to the hot water heater. Replace bathroom exhaust fan with whispergreen ASHRAE fan and install motion sensor. Fan needs to be wired for continuous run. Vent bath fan using 4" rigid metal pipe, vent needs to go through roof, vent pipe must also be insulated to R-8.	6/18/24	6/21/24

071124-01	NO	YES	<p>Replace existing HVAC equipment with 10Kw furnace and 2 ton heatpump. Install New Disconnect and whip on outdoor unit use existing power wire for unit. Run new drain line to outside of underpinning. Size breakers according to data plate. Build sheet metal box to set on top of furnace and seal to furnace and seal plenum below the furnace with mastic. Install filter grill and patch bottom with sheet metal to allow furnace door to come off. Seal lineset penetrations. Add overflow safety switch to a-coil drain pan and insulate entire drain line and tape seams where insulation meets with lineset tape. Install Whispergreen bath fan and motion sensor. Wire fan for continuous run. Vent through the roof and insulate with r-8 duct wrap. Replace existing wire with 10-2. Install new 30 amp breaker disconnect and whip.</p>	7/29/2024	8/1/2024
-----------	----	-----	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------	----------